

Recommended Standard schedule of Basic rates for PIJF U/G Copper Cable construction works in Chennai telephones for the year 2017-2018

SL.NO.	ITEM CODE	Description	UNIT	Rates recommended by Committee for approval
				In Rs.
8	9DOC	Documentation (6 Copies of Bound Document = 1 Set)	one set	1697.00
Note: The Document shall be done as per Specifications and Scope defined in Item 11 of Section VII for all the Work against Work Order issued in accordance with the Item 1.0 of Section VI				
9	HDD1	Upto 60mm dia/ 200 pair cable	Per meter	500.00
	HDD2	61 to 100mm dia/ 400 pair cable	Per meter	500.00
	HDD3	151mm to 200mm dia / 800 or 1200 Pair cable	Per meter	700.00
	HDD4	151mm to 200mm dia /for Multiple cables. 3x200 / 2x400 Pair Cable	Per meter	700.00
10		Trenching trial pits for locating cable		
		Trenching trial pits locating the existing / faulty UG Cable of Trench size(45 cm top 30 cm bottom & 100 cm Depth) for kutcha surface		116.50
		Trenching trial pits locating the existing / faulty UG Cable of Trench size(45 cm top 30 cm bottom & 100 cm Depth) for Hard Soil / Asphalt area		184.49
		Trenching trial pits locating the existing / faulty UG Cable of Trench size(45 cm top 30 cm bottom & 100 cm Depth) for Soft integrated rock / Cemented area		218.29
11		Trenching pits for exposing existing cable		
		(Cases where no further operation on cables is involved)		310.67
		Trenching pit for exposing the existing / faulty UG Cable for kutcha surface	Per cum	491.97
		Trenching pit for exposing the existing / faulty UG Cable for Asphalt area	Per cum	582.11
		Trenching pit for exposing the existing / faulty UG Cable for Cemented area	Per cum	
The above rate includes trenching, backfilling, compacting, levelling, removing excess earth from the site, watering, dewatering, diversion of traffic, arranging night signal & Caution boards etc.				
12		Night Patrolling for exposed and unburied higher sized distribution and primary cables due to Corporation / High way/other agencies work	Per person	648.04